

Annexure'B'			
SCHEDULE FOR ERECTION OF 10 MTRS. PSC POLES			2022-23
Sr. No.	Description	Unit	Rate 2022-23
1	Erection of PSC Pole of 10Mtr. 270Kg. Including excavation iof PIT and refilling of Earth, Fixing of cross arms, Top fitting Clamps Anti-climbing devices, Insulators etc. complete and paiting of fabaricated materials used on the poles and numbering with cost of paint as per standard specification but excluding erectin of Guy set and Earthing	Nos.	1720
2	Erection of Double pole structure of 10Mtr. 270Kg. PSC poles including excavation of PITS & refilling of earthing, Fixing of Channels, Supporing Angles, Clamps, Anti-Climbing devices Danger Boards, Insulators etc. complete and painting of fabricated materials used on the poles and numbering with cost of paint as per standard speicification but excluding erection of Guy sets and Earthing (W/O AB Switch)	Nos.	3908
3	Erection of Double pole structure with mounting of AB switch, DO Fuses of 10Mtr. 270Kg. PSC poles including excavation of pits and refilling of earth fixing of Channels supporting Angles, Clamps, Anti-Climbing devices, Danger boards, Insulators, DO Fuses etc. complete and painting of fabricated materials used on the poles and numbering with cost of paint as per standard speicification but excluding erection of Guy set and Earthing.	Nos.	4702
4	Erection of Double pole structures with mounting of DO Fuses, Transformers, Lighting Arrestors, Dist. Box etc. of 10Mtr. 270Kg. . PSC Poles including excavation of pits and refilling of Earth, Carting of Transformers from Stores to Site, Fixing of Channels, Supporting Angles, Bracing cross Arms, Clamps, Anticlimbing Devices Danger boards, conductor and cable wiring etc. complete and painting of fabricated materials used on the poles and numbering with cost of paint as per standard specification but excluding erection of Guy sets and Earthing.	Nos.	9242
	Recarting of 8mtr psc pole within sdn area		